BRUHAT BENGALURU MAHANAGARA PALIKE

Name of work:- Improvements and Asphalting to roads at Ambhabhavani nagara and Ambhabhavani Layout and surrounding areas in Attur ward No-03

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
1	KSRRB 300-3. **Earthwork excavation** by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 143/ Item No. 19.1/ PWD SR 2018-19								
		Cum							
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80	1.10	1.00	184.36		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00	1.10	1.00	66.00		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra		1	171.00	1.10	1.00	188.10		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50	1.10	1.00	97.90		
	Culverts								
	Subhas Chandra Bose Road								
	3rd cross road		1	7.80	1.40	1.00	10.92		
	2nd cross road		1	6.40	1.40	1.00	8.96		
	1st cross road		1	5.90	1.40	1.00	8.26		
	7th cross road		1	7.70	1.40	1.00	10.78		
	6th cross road		1	8.80	1.40	1.00	12.32		
	Jyoti Naidu Layout		1	6.30	1.40	1.00	8.82		
	Ambabavani Temple Opposite		1	5.00	1.40	1.00	7.00		
	Laxmaiyya Reddy Layout		1	6.00	1.40	1.00	8.40		
	Over burden earth								
	cross Road		1	30.00	1.08	0.30	9.68		
	2nd Cross		1	87.00	1.10	0.30	28.71		
	Jyoti Nagara 2stage main road		1	116.00	1.00	0.30	34.80		
	2nd Cross		1	87.00	1.00	0.30	26.10		
	5th Cross		1	88.00	1.00	0.30	26.40		
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Rain water Harvesting pit								
	Inside drain								
	Perculation pit dia-0.60m		26	(3.14x0.60^2/4)		0.90	6.61		
	Over burden		26	0.90	0.90	0.40	8.42		
							752.54	219.93	165505.62
	Basic Rate	130.00							
	Loading & Unloading	57.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	12.45							
	Total Rate	219.93							
2	KSRB 2.8 : Providing and **Filling in foundation with granite / trap broken metal 100mm.** and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS 2.10.2 KPWD S.R 2018-19 Page No. 7 I.No. 2.15								
	Inside drain	Cum							
	Perculation pit dia-0.60m		26	(3.14x0.60^2/4)		0.30	2.20		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
							2.20	2574.74	5755.38
	Basic Rate	2429.00							
	Area Weightage @ 6%	145.74							
	Total	2574.74							
3	Providing Nominal 40mm size stone aggrigates (Page no II, Sl NO.25)Code NO.0750								
	Inside drain	Cum							
	0.6		26	(3.14x0.60^2/4)		0.30	2.20		
							2.20	1091.43	2405.82
	Basic Rate	1091.43							
	Total	1091.43							
4	Providing Nominal 20mm size stone aggrigates (Page no II, Sl NO.28) Code NO.0749								
	Inside drain	Cum							
	0.6		26	(3.14x0.60^2/4)		0.30	2.20		
							2.20	1091.43	2405.82
	Basic Rate	1091.43							
	Total	1091.43							
5	KSRB 7.9 : Providing And fixing ms grill work for windows and ventilators using ms flats or ms square rods or combination of ms flats and square rods as per approved design drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials fixtures, labours, and complete as per specifications page no.34 item no.7.9								
	Inside drain	Kgs							
	0.6		26	0.60	0.60		9.36		
	21 Kgs/Sqm						196.56		
							196.56	100.70	19793.59
	Basic Rate	95.00							
	Area Weightage @ 6%	5.70							
	Total	100.70							
6	KSRRB M2900-1. Plain cement concrete 1:3:6 mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications MORTH Specification No. 408 KPWD S.R 2018-19 Page No. 254 I.No. 34.1								
		Cum							
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80	1.10	0.15	27.65		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00	1.10	0.15	9.90		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		1	171.00	1.10	0.15	28.22		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50	1.10	0.15	14.69		
	Culverts								
	Subhas Chandra Bose Road								
	3rd cross road		1	7.80	1.40	0.15	1.64		
	2nd cross road		1	6.40	1.40	0.15	1.34		
	1st cross road		1	5.90	1.40	0.15	1.24		
	7th cross road		1	7.70	1.40	0.15	1.62		
	6th cross road		1	8.80	1.40	0.15	1.85		
	Jyoti Naidu Layout		1	6.30	1.40	0.15	1.32		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Ambabavani Temple Opposite		1	5.00	1.40	0.15	1.05		
	Laxmaiyya Reddy Layout		1	6.00	1.40	0.15	1.26		
	PCC For Kerbs								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80	0.20	0.075	2.51		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00	0.20	0.075	0.90		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		1	171.00	0.20	0.075	2.57		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50	0.20	0.075	1.34		
							99.09	**4479.56**	**443866.16**
	Basic Rate	4226.00							
	Area Weightage @ 6 %	253.56							
	Total Rate	4479.56							

7	Providing and laying plain/reinforced cement concrete for side drains using **M20** nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.**Wall & bottom thickness 15cm** KPWD S.R 2018-19 Page No. 271 I.No. 37.59.2								
		Cum							
	For Raft								
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80	1.00	0.15	25.14		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00	1.00	0.15	9.00		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		1	171.00	1.00	0.15	25.65		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50	1.00	0.15	13.35		
	For Side wall								
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		4	83.80	0.15	0.60	30.17		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		4	30.00	0.15	0.60	10.80		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		2	171.00	0.15	0.60	30.78		
	Lakshmaiah Reddy Layout 2nd Cross Road		4	44.50	0.15	0.60	16.02		
	For Raft								
	Culverts								
	Subhas Chandra Bose Road								
	3rd cross road		1	7.80	1.20	0.25	2.34		
	2nd cross road		1	6.40	1.20	0.25	1.92		
	1st cross road		1	5.90	1.20	0.20	1.42		
	7th cross road		1	7.70	1.20	0.20	1.85		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	6th cross road		1	8.80	1.20	0.25	2.63		
	Jyoti Naidu Layout		1	6.30	1.20	0.25	1.89		
	Ambabavani Temple Opposite		1	5.00	1.20	0.25	1.50		
	Laxmaiyya Reddy Layout		1	6.00	1.20	0.25	1.80		
	For Side wall								
	Culverts								
	Subhas Chandra Bose Road								
	3rd cross road		2	7.80	0.25	0.60	2.34		
	2nd cross road		2	6.40	0.25	0.60	1.92		
	1st cross road		2	5.90	0.25	0.60	1.77		
	7th cross road		2	7.70	0.25	0.60	2.31		
	6th cross road		2	8.80	0.25	0.60	2.64		
	Jyoti Naidu Layout		2	6.30	0.25	0.60	1.89		
	Ambabavani Temple Opposite		2	5.00	0.25	0.60	1.50		
	Laxmaiyya Reddy Layout		2	6.00	0.25	0.60	1.80		
							192.42	**7070.20**	**1360462.02**
	Basic Rate	6670.00							
	Area Weightage @ 6 %	400.20							
	Total Rate	7070.20							
8	KSRRB M2200-6. Providing **T.M.T**. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 **TMT Bars Fe 550**(P-229/28.8.3) PWD SR 2018-19								
		Tn							
	For RCC Drain								
	Total RCC Quantity	Cum					159.60		
		Kg					60.00		
		Kg					9576.00		
							9.58	**72940.72**	**698480.33**
	For RCC Culvert								
	Total RCC Quantity	Cum					31.51		
		Kg					70.00		
		Kg					2205.98		
							2.21	**72940.72**	**160905.77**
	Basic Rate	68812.00							
	Area Weightage @ 6 %	4128.72							
	Total Rate	72940.72							
9	Providing & laying **precast drain cover slab of 100 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.9 x 0.60 x 0.1)Data rate								
		Sqm							
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80	0.90		150.84		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00	0.90		54.00		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		1	171.00	0.90		153.90		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50	0.90		80.10		
	missing slabs for old drain		1	56.00	0.90		50.40		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
							489.24	2337.00	1143353.88
	Data Rate	2337.00							
10	Providing & laying **precast drain cover slab of 250 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.60 x 0.25)Data rate								
		Sqm							
	Culverts								
	Subhas Chandra Bose Road								
	3rd cross road		1	7.80	1.20		9.36		
	2nd cross road		1	6.50	1.20		8.80		
	7th cross road		1	7.70	1.20		9.24		
							27.40	5418.00	148453.20
	Data Rate	5418.00							
11	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)								
		No's							
	New Drain								
	Jyoti Nagar 1st cross road OPP to Amba Bhavani Temple Road		2	83.80			167.60		
	Cross road at Jyoti Nagar 1st cross Opp to Amba Bhavani Temple Road		2	30.00			60.00		
	Connecting Road Lakshmaiah Reddy Layout to Subhas Chandra Bose Main Road		1	171.00			171.00		
	Lakshmaiah Reddy Layout 2nd Cross Road		2	44.50			89.00		
	Total Length						487.60		
	Total Length / 0.45						1084.00		
							1084.00	432.48	468808.32
	Basic Rate	408.00							
	Area Weightage @ 6 %	24.48							
	Total Rate	432.48							
12	KSRRB 800-1. Painting **two coats** after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Page No. 180/ Item No. 24.1/ PWD SR 2018-19								
		Sqm							
	Total Length		1	487.60		0.30	146.28		
							146.28	84.80	12404.54
	Basic Rate	80.00							
	Area Weightage @ 6 %	4.80							
	Total Rate	84.80							
	ASPHALT ROAD								

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
13	KSRRB M300-14. **Excavation for roadwork** in all types of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications. MORTH Specification No.301(pg no-143,S.Lno-19.14)KPWD S.R 2018-19								
		Cum							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80	0.50	2265.30		
	Sai Nagara 1st cross road		1	238.40	7.00	0.50	834.40		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00	0.55	301.95		
	3rd cross road		1	95.00	6.60	0.50	313.50		
	Laxmaiyya Reddy Layout		1	180.00	6.00	0.50	540.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10	0.50	96.57		
							4351.72	**65.17**	**283596.55**
	Basic Rate	41.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	3.69							
	Total Rate	65.17							
14	KSRRB 300-58. **Compaction of original ground** with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 (I No-19.64,P No-147)								
		Sqm							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80		4530.60		
	Sai Nagara 1st cross road		1	238.40	7.00		1668.80		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00		549.00		
	3rd cross road		1	95.00	6.60		627.00		
	Laxmaiyya Reddy Layout		1	180.00	6.00		1080.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10		192.76		
							8648.16	**6.36**	**55002.30**
	Basic rate	6.00							
	Area Weightage 6%	0.36							
	Total	**6.36**							
15	Construction of **granular sub-base Grading-V** as sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision. Page No. 153/ Item No. 20.5/ PWD SR 2018-19								
		Cum							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80	0.15	679.59		
	Sai Nagara 1st cross road		1	238.40	7.00	0.15	250.32		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00	0.15	82.35		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	3rd cross road		1	95.00	6.60	0.15	94.05		
	Laxmaiyya Reddy Layout		1	180.00	6.00	0.15	162.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10	0.15	28.91		
							1297.22	1994.92	2587858.10
	Basic Rate	1882.00							
	Area Weightage @ 6 %	112.92							
	Total Rate	1994.92							
16	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 Page No. 155/ Item No. 20.18/ PWD SR 2018-19								
		Cum							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80	0.23	1042.04		
	Sai Nagara 1st cross road		1	238.40	7.00	0.23	383.82		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00	0.23	126.27		
	3rd cross road		1	95.00	6.60	0.23	144.21		
	Laxmaiyya Reddy Layout		1	180.00	6.00	0.23	248.40		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10	0.23	44.33		
							1989.08	2001.28	3980699.62
	Basic Rate	1888.00							
	Area Weightage @ 6 %	113.28							
	Total Rate	2001.28							
17	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM ,including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per Specifications. MORTH Specification No. 502 Complete with all lead and lift and as per the direction of the Engineer-in-Charge. Page No. 158/ Item No. 21.6/ PWD SR 2018-19 Issue Rates								
		Sqm							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80		4530.60		
	Sai Nagara 1st cross road		1	238.40	7.00		1668.80		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00		549.00		
	3rd cross road		1	95.00	6.60		627.00		
	Laxmaiyya Reddy Layout		1	180.00	6.00		1080.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10		192.76		
							8648.16	29.68	256677.39
	Basic Rate	28.00							
	Area Weightage @ 6 %	1.68							
	Total Rate	29.68							

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
18	KSRRB M500-17. Providing and laying **dense graded bituminous macadam** using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. Clause 505 of morth V revision using 40/60 TPH capacity H.M.P. with mechanical paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen. Page No. 160/ Item No. 21.17.6/ PWD SR 2018-19 Issue Rates								
		Cum							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80	0.05	226.53		
	Sai Nagara 1st cross road		1	238.40	7.00	0.05	83.44		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00	0.05	27.45		
	3rd cross road		1	95.00	6.60	0.05	31.35		
	Laxmaiyya Reddy Layout		1	180.00	6.00	0.05	54.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10	0.05	9.64		
							432.41	**6407.70**	**2770740.74**
	Basic Rate	6045.00							
	Area Weightage @ 6 %	362.70							
	Total Rate	6407.70							
19	KSRRB 500-2. **Cleaning the existing black** topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 Page No. 158/ Item No. 21.2/ PWD SR 2018-19								
		Sqm							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80		4530.60		
	Sai Nagara 1st cross road		1	238.40	7.00		1668.80		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00		549.00		
	3rd cross road		1	95.00	6.60		627.00		
	Laxmaiyya Reddy Layout		1	180.00	6.00		1080.00		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10		192.76		
							8648.16	**5.30**	**45835.25**
	Basic Rate	5.00							
	Area Weightage @ 6 %	0.30							
	Total Rate	5.30							
20	KSRRB 500-7. Providing and applying **tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5 Page No. 158/ Item No. 21.7/ PWD SR 2018-19 Issue Rates								
		Sqm							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80		4530.60		
	Sai Nagara 1st cross road		1	238.40	7.00		1668.80		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00		549.00		
	3rd cross road		1	95.00	6.60		627.00		
	Laxmaiyya Reddy Layout		1	180.00	6.00		1080.00		

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Laxmaiyya Reddy Cross Road		1	31.60	6.10		192.76		
							8648.16	**12.72**	**110004.60**
	Basic Rate	12.00							
	Area Weightage @ 6 %	0.72							
	Total Rate	12.72							
21	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision. -using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen (Pg:162, It.No-21.22.6 PWD SR:2018-19)Issue Rates								
		Cum							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		1	419.50	10.80	0.03	135.92		
	Sai Nagara 1st cross road		1	238.40	7.00	0.03	50.06		
	Jyoti Nagara 2stage main road								
	4th cross road		1	91.50	6.00	0.03	16.47		
	3rd cross road		1	95.00	6.60	0.03	18.81		
	Laxmaiyya Reddy Layout		1	180.00	6.00	0.03	32.40		
	Laxmaiyya Reddy Cross Road		1	31.60	6.10	0.03	5.78		
							259.44	**7355.34**	**1908304.72**
	Basic Rate	6939.00							
	Area Weightage @ 6 %	416.34							
	Total Rate	7355.34							
22	KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 Page No. 182/ Item No. 24.15 PWD SR 2018-19								
		Sqm							
	New Road								
	Ambhabavani Nagara								
	Subhas Chandra Bose main road		2.5	419.50	0.10		104.88		
	Sai Nagara 1st cross road		2.5	238.40	0.10		59.60		
	Jyoti Nagara 2stage main road								
	4th cross road		2.5	91.50	0.10		22.88		
	3rd cross road		2.5	95.00	0.10		23.75		
	Laxmaiyya Reddy Layout		2.5	180.00	0.10		45.00		
	Laxmaiyya Reddy Cross Road		2.5	31.60	0.10		7.90		
							264.00	**454.74**	**120051.36**
	Basic Rate	429.00							

SL.No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Area Weightage @ 6 %	25.74							
	Total Rate	454.74							
								Sub Total-A	16,751,371.09
								Tender Premium 5%	837,568.55
								GST 12%	2,010,164.53
								DPR 1%	200,000.00
								PMC 1%	200,000.00
								Miscellaneous	895.83
								Total	20,000,000.00

VSR CIVIL INFRA PVT. LTD. BANGALORE

Consultant

Assistant Engineer
Ward No. 3

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪವಿಭಾಗ,
ಬ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು-೧೦೬

Asst.Executive Engineer
Yelahanka Sub Division

Executive Engineer
Yelahanka Division

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

BRUHAT BENGALURU MAHANAGARA PALIKE

Name of work:- Improvements to roads and Asphalting to Siddaruda mata and Prakruthi layout in Attur ward no-03

Sl. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
1	KSRRB 300-3. **Earthwork excavation** by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 143/ Item No. 19.1/ PWD SR 2018-19								
		Cum							
	New Drain								
	Prakruti layout								
	Connecting Main Road		2	129.00	1.10	1.10	312.18		
	4th Cross road From Dead End		2	17.20	1.10	1.00	37.84		
	Main Road LHS		1	13.00	1.10	1.00	14.30		
	3rd cross road		2	17.00	1.10	1.00	37.40		
	2nd cross road		2	92.00	1.10	1.00	202.40		
	1st Cross Road		2	48.00	1.10	1.10	116.16		
	1st cross Road (sub Road)		2	21.10	1.10	1.00	46.42		
	Bhaskar Reddy layout								
	Entrance Road		2	142.00	1.10	1.10	343.64		
	Infront of Jaaji House		2	31.00	1.10	1.10	75.02		
	Connecting road to Jaaji House		2	46.00	1.10	1.10	111.32		
	Subhas Chandra Bose Road(RHS)		1	365.00	1.10	1.00	401.50		
	Subhas Chandra Bose Road(LHS)		1	205.00	1.10	1.00	225.50		
	Jyoti Nagara 2stage main road (RHS)		1	123.00	1.10	1.00	135.30		
	2nd cross Road		2	86.50	1.10	1.00	190.30		
	Culverts								
	Prakruti Layout								
	Main Road Culvert		1	7.10	1.40	1.00	9.94		
	1st cross road		1	7.30	1.40	1.00	10.22		
	2nd cross road		1	7.80	1.40	1.00	10.92		
	3rd cross road		1	7.30	1.40	1.00	10.22		
	Bhaskar Reddy Layout								
	Jaaji house cross		1	8.90	1.40	1.00	12.46		
	Connecting road to Jaaji House		1	8.00	1.40	1.00	11.20		
	Main Road		1	7.70	1.40	1.00	10.78		
	Desilting								
	Entrance Road		2	90.00	0.60	0.50	54.00		
	Over burden earth								
	Entrance Road		1	90.00	1.03	0.30	27.65		
	Inside drain								
	Perculation pit dia-0.60m		65	(3.14x0.60^2/4)		0.90	16.53		
	Over burden		65	0.90	0.90	0.40	21.06		
							2444.26	219.93	537,563.63
	Basic Rate	130.00							
	Loading & Unloading	57.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	12.45							
	Total Rate	219.93							
2	KSRB 2.8 : Providing and **Filling in foundation with granite / trap broken metal 100mm.** and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS 2.10.2 KPWD S.R 2018-19 Page No. 7 I.No. 2.15								
	Inside drain	Cum							
	Over burden		65	(3.14x0.60^2/4)		0.30	5.51		
							5.51	2574.74	14188.62
	Basic Rate	2429.00							
	Area Weightage @ 6%	145.74							

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PALIKE

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Total	2574.74							
3	Providing Nominal 40mm size stone aggrigates (Page no II, SI NO.25)Code NO.0750								
	Inside drain	Cum							
	Over burden		65	(3.14x0.60^2/4)		0.30	5.51		
							5.51	1091.43	6014.54
	Basic Rate	1091.43							
	Total	1091.43							
4	Providing Nominal 20mm size stone aggrigates (Page no II, SI NO.28) Code NO.0749								
	Inside drain	Cum							
	Over burden		65	(3.14x0.60^2/4)		0.30	5.51		
							5.51	1091.43	6014.54
	Basic Rate	1091.43							
	Total	1091.43							
5	KSRB 7.9 : Providing And fixing ms grill work for windows and ventilators using ms flats or ms square rods or combination of ms flats and square rods as per approved design drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials fixtures, labours, and complete as per specifications page no.34 item no.7.9								
	Inside drain	Kgs							
	Over burden		65	0.60	0.60		23.40		
	21 Kgs/Sqm						491.40		
							491.40	100.70	49483.98
	Basic Rate	95.00							
	Area Weightage @ 6%	5.70							
	Total	100.70							
6	KSRRB M2900-1. Plain cement concrete 1:3:6 mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications MORTH Specification No. 408 KPWD S.R 2018-19 Page No. 254 I No. 34.1								
		Cum							
	New Drain								
	Prakruti layout								
	Connecting Main Road		2	129.00	1.10	0.15	42.57		
	4th Cross road From Dead End		2	17.20	1.10	0.15	5.68		
	Main Road LHS		1	13.00	1.10	0.15	2.15		
	3rd cross road		2	17.00	1.10	0.15	5.61		
	2nd cross road		2	92.00	1.10	0.15	30.36		
	1st Cross Road		2	48.00	1.10	0.15	15.84		
	1st cross Road (sub Road)		2	21.10	1.10	0.15	6.96		
	Bhaskar Reddy layout								
	Entrance Road		2	142.00	1.10	0.15	46.86		
	Infront of Jaaji House		2	31.00	1.10	0.15	10.23		
	Connecting road to Jaaji House		2	46.00	1.10	0.15	15.18		
	Subhas Chandra Bose Road(RHS)		1	365.00	1.10	0.15	60.23		
	Subhas Chandra Bose Road(LHS)		1	205.00	1.10	0.15	33.83		
	Jyoti Nagara 2stage main road (RHS)		1	123.00	1.10	0.15	20.30		
	2nd cross Road		2	86.50	1.10	0.15	28.55		
	Culverts								
	Prakruti Layout								
	Main Road Culvert		1	7.10	1.40	0.15	1.49		
	1st cross road		1	7.30	1.40	0.15	1.53		
	2nd cross road		1	7.80	1.40	0.15	1.64		
	3rd cross road		1	7.30	1.40	0.15	1.53		
	Bhaskar Reddy Layout								
	Jaaji house cross		1	8.90	1.40	0.15	1.87		
	Connecting road to Jaaji House		1	8.00	1.40	0.15	1.68		
	Main Road		1	7.70	1.40	0.15	1.62		
	PCC For Kerbs								
	Prakruti layout								

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Connecting Main Road		2	129.00	0.20	0.075	3.87		
	4th Cross road From Dead End		2	17.20	0.20	0.075	0.52		
	Main Road LHS		1	13.00	0.20	0.075	0.20		
	3rd cross road		2	17.00	0.20	0.075	0.51		
	2nd cross road		2	92.00	0.20	0.075	2.76		
	1st Cross Road		2	48.00	0.20	0.075	1.44		
	1st cross Road (sub Road)		2	21.10	0.20	0.075	0.63		
	Bhaskar Reddy layout								
	Entrance Road		2	142.00	0.20	0.075	4.26		
	Infront of Jaaji House		2	31.00	0.20	0.075	0.93		
	Connecting road to Jaaji House		2	46.00	0.20	0.075	1.38		
	Subhas Chandra Bose Road(RHS)		1	365.00	0.20	0.075	5.48		
	Subhas Chandra Bose Road(LHS)		1	205.00	0.20	0.075	3.08		
	Jyoti Nagara 2stage main road (RHS)		1	123.00	0.20	0.075	1.85		
	2nd cross Road		2	86.50	0.20	0.075	2.60		
							365.17	4479.56	1,635,796.45
	Basic Rate	4226.00							
	Area Weightage @ 6 %	253.56							
	Total Rate	4479.56							
7	Providing and laying plain/reinforced cement concrete for side drains using **M20** nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.**Wall & bottom thickness 15cm** KPWD S.R 2018-19 Page No. 271 I No. 37.59 2									
		Cum							
	For Raft								
	New Drain								
	Prakruti layout								
	Connecting Main Road		2	129.00	0.90	0.15	34.83		
	4th Cross road From Dead End		2	17.20	0.90	0.15	4.64		
	Main Road LHS		1	13.00	0.90	0.15	1.76		
	3rd cross road		2	17.00	0.90	0.15	4.59		
	2nd cross road		2	92.00	0.90	0.15	24.84		
	1st Cross Road		2	48.00	0.90	0.15	12.96		
	1st cross Road (sub Road)		2	21.10	0.90	0.15	5.70		
	Bhaskar Reddy layout								
	Entrance Road		2	142.00	0.90	0.15	38.34		
	Infront of Jaaji House		2	31.00	0.90	0.15	8.37		
	Connecting road to Jaaji House		2	46.00	0.90	0.15	12.42		
	Subhas Chandra Bose Road(RHS)		1	365.00	0.90	0.15	49.28		
	Subhas Chandra Bose Road(LHS)		1	205.00	0.90	0.15	27.68		
	Jyoti Nagara 2stage main road (RHS)		1	123.00	0.90	0.15	16.61		
	2nd cross Road		2	86.50	0.90	0.15	23.36		
	For Side wall								
	New Drain								
	Prakruti layout								
	Connecting Main Road		4	129.00	0.15	0.60	46.44		
	4th Cross road From Dead End		4	17.20	0.15	0.60	6.19		
	Main Road LHS		2	13.00	0.15	0.60	2.34		
	3rd cross road		4	17.00	0.15	0.60	6.12		
	2nd cross road		4	92.00	0.15	0.60	33.12		
	1st Cross Road		4	48.00	0.15	0.60	17.28		
	1st cross Road (sub Road)		4	21.10	0.15	0.60	7.60		
	Bhaskar Reddy layout								
	Entrance Road		4	142.00	0.15	0.60	51.12		
	Infront of Jaaji House		4	31.00	0.15	0.60	11.16		
	Connecting road to Jaaji House		4	46.00	0.15	0.60	16.56		
	Subhas Chandra Bose Road(RHS)		2	365.00	0.15	0.60	65.70		
	Subhas Chandra Bose Road(LHS)		2	205.00	0.15	0.60	36.90		
	Jyoti Nagara 2stage main road (RHS)		2	123.00	0.15	0.60	22.14		

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	2nd cross Road		4	86.50	0.15	0.60	31.14		
	Culvert Raft								
	Prakruti Layout								
	Main Road Culvert		1	7.10	1.20	0.25	2.13		
	1st cross road		1	7.30	1.20	0.25	2.19		
	2nd cross road		1	7.80	1.20	0.25	2.34		
	3rd cross road		1	7.30	1.20	0.25	2.19		
	Bhaskar Reddy Layout								
	Jaaji house cross		1	8.90	1.20	0.25	2.67		
	Connecting road to Jaaji House		1	8.00	1.20	0.25	2.40		
	Main Road		1	7.70	1.20	0.25	2.31		
	Culvert Side wall								
	Prakruti Layout								
	Main Road Culvert		2	7.10	0.25	0.60	2.13		
	1st cross road		2	7.30	0.25	0.60	2.19		
	2nd cross road		2	7.80	0.25	0.60	2.34		
	3rd cross road		2	7.30	0.25	0.60	2.19		
	Bhaskar Reddy Layout								
	Jaaji house cross		2	8.90	0.25	0.60	2.67		
	Connecting road to Jaaji House		2	8.00	0.25	0.60	2.40		
	Main Road		2	7.70	0.25	0.60	2.31		
							651.62	**7070.20**	**4,607,112.00**
	Basic Rate	6670.00							
	Area Weightage @ 6 %	400.20							
	Total Rate	7070.20							
8	KSRRB M2200-6. Providing **T.M.T.** steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 **TMT Bars Fe 550**(P-229/28.8.3) PWD SR 2018-19								
		Tn							
	For RCC Drain								
	Total RCC Quantity	Cum					**618.50**		
		Kg					60.00		
		Kg					37110.00		
							37.11	**72940.72**	**2,706,830.12**
	For RCC Drain								
	Total RCC Quantity	Cum					**32.04**		
		Kg					70.00		
		Kg					2242.80		
							2.24	**72940.72**	**163,591.45**
	Basic Rate	68812.00							
	Area Weightage @ 6 %	4128.72							
	Total Rate	72940.72							
9	Providing & laying **precast drain cover slab of 100 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer in Charge.(0.9 x 0.60 x 0.1)Data rate								
		Sqm							
	New Drain								
	Prakruti layout								
	Connecting Main Road								
	4th Cross road From Dead End		2	129.00	0.90		232.20		
	Main Road LHS		2	17.20	0.90		30.96		
	3rd cross road		1	13.00	0.90		11.70		
	2nd cross road		2	17.00	0.90		32.13		
	1st Cross Road		2	92.00	0.90		165.60		
	1st cross Road (sub Road)		2	48.00	0.90		86.40		
	Bhaskar Reddy layout		2	21.10	0.90		37.98		
	Entrance Road								
	Infront of Jaaji House		2	142.00	0.90		255.60		
			2	31.00	0.90		55.80		

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Connecting road to Jaaji House		2	46.00	0.90		82.80		
	Subhas Chandra Bose Road(RHS)		1	365.00	0.90		328.50		
	Subhas Chandra Bose Road(LHS)		1	205.00	0.90		184.50		
	Jyoti Nagara 2stage main road (RHS)		1	123.00	0.90		110.70		
	2nd cross Road		2	86.50	0.90		155.70		
	slabs for old drain		2	157.50	0.90		283.50		
							2054.07	2337.00	4,800,361.59
	Data Rate	2337.00							
10	Providing & laying **precast drain cover slab of 250 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.60 x 0.25)Data rate								
		Sqm							
	CULVERTS								
	Prakruti Layout								
	Main Road Culvert		1	7.10	1.20		8.52		
	1st cross road		1	7.30	1.20		9.04		
	2nd cross road		1	7.80	1.20		9.36		
	3rd cross road		1	7.30	1.20		9.04		
							35.96	5418.00	194,831.28
	Data Rate	5418.00							
11	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)								
		No's							
	New Kerbs								
	Prakruti layout								
	Connecting Main Road		2	129.00			258.00		
	4th Cross road From Dead End		2	17.20			34.40		
	Main Road LHS		1	13.00			13.00		
	3rd cross road		2	17.00			34.00		
	2nd cross road		2	92.00			184.00		
	1st Cross Road		2	48.00			96.00		
	1st cross Road (sub Road)		2	21.10			42.20		
	Bhaskar Reddy layout								
	Entrance Road		2	142.00			284.00		
	Infront of Jaaji House		2	31.00			62.00		
	Connecting road to Jaaji House		2	46.00			92.00		
	Subhas Chandra Bose Road(RHS)		1	365.00			365.00		
	Subhas Chandra Bose Road(LHS)		1	205.00			205.00		
	Jyoti Nagara 2stage main road (RHS)		1	123.00			123.00		
	2nd cross Road		2	86.50			173.00		
	New kerbs for old drain		2	46.00			92.00		
				Total Length			2057.60		
				No of kerbs= Total Length/0.45			4572.44	432.48	1,977,490.77
	Basic Rate	408.00							
	Area Weightage @ 6 %	24.48							
	Total Rate	432.48							
12	KSRRB 800-1. Painting **two coats** after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Page No. 180/ Item No. 24.1/ PWD SR 2018-19								
		Sqm							
	Total Length		1	2057.60		0.30	617.28		
	Basic Rate	80.00					617.28	84.80	51,957.57

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
								Sub Total-A	16,751,236.55
								Tender Premium 5%	837,561.83
								GST 12%	2,010,148.39
								DPR 1%	200,000.00
								PMC 1%	200,000.00
								Miscellaneous	1,053.24
								Total	20,000,000.00

VSR CIVIL INFRA PVT LTD BANGALORE Consultant

Assistant Engineer
Ward No. 3

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪವಿಭಾಗ, ಬೆಂಗಳೂರು.
Yelahanka Sub Division

Executive Engineer
Yelahanka Divison

BRUHAT BENGALURU MAHANAGARA PALIKE

Name of work:- Comprehensive development of roads and drains in Best county -1,2,3 and surrounding areas in Attur ward no-03

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
1	KSRRB 300-3. **Earthwork excavation** by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 143/ Item No. 19.1/ PWD SR 2018-19								
		Cum							
	New Drain								
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40	1.10	1.00	119.24		
	5th Cross Road		2	88.00	1.10	1.00	193.60		
	7th cross Road		1	106.00	1.10	1.00	116.60		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00	1.10	1.00	305.80		
	12th cross road		1	15.00	1.10	1.00	16.50		
	Best county-2								
	Vinayaka Temple		1	49.40	1.10	1.00	54.34		
	1st Main Road		1	456.50	1.10	1.00	502.15		
	Cross Road		2	43.00	1.10	1.00	94.60		
	Over burden earth								
	cross Road		1	30.00	1.00	0.30	9.00		
	7th Cross Road		1	106.20	1.10	0.30	35.05		
	Jyoti Nagar 1st cross road		1	84.00	0.85	0.20	14.28		
	Culverts								
	Subhas Chandra Bose Road								
	8th corss road		1	8.80	1.40	1.00	12.32		
	Subhas Chandra Bose Road LHS								
	2nd cross road		1	6.50	1.40	1.00	9.10		
	3rd cross road		1	4.00	1.40	1.10	6.16		
	4th cross road		1	6.70	1.40	1.10	10.32		
	5th cross road		1	6.80	1.40	1.10	10.47		
	6th cross road		1	7.00	1.40	1.10	10.78		
	7th cross road		1	9.00	1.40	1.10	13.86		
	Best County		1	9.00	1.40	1.00	12.60		
	Rain water Harvesting pit								
	Inside drain								
	Perculation pit dia-0.60m		50	(3.14x0.60^2/4)		0.90	12.72		
	Over burden		50	0.90	0.90	0.40	16.20		
							1575.68	219.93	346,538.07
	Basic Rate	130.00							
	Loading & Unloading	57.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	12.45							
	Total Rate	219.93							
2	KSRB 2.8 : Providing and **Filling in foundation with granite / trap broken metal 100mm.** and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS 2.10.2 KPWD S.R 2018-19 Page No. 7 I.No. 2.15								
	Inside drain	Cum							

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Perculation pit dia-0.60m		50	(3.14x0.60^2/4)		0.30	4.24		
							4.24	2574.74	10914.32
	Basic Rate	2429.00							
	Area Weightage @ 6%	145.74							
	Total	2574.74							
3	Providing Nominal **40mm size stone** aggrigates (Page no II, SI NO.25)Code NO.0750								
	Inside drain	Cum							
	Perculation pit dia-0.60m		50	(3.14x0.60^2/4)		0.30	4.24		
							4.24	1091.43	4626.57
	Basic Rate	1091.43							
	Total	1091.43							
4	Providing Nominal **20mm size stone** aggrigates (Page no II, SI NO.28) Code NO.0749								
	Inside drain	Cum							
	Perculation pit dia-0.60m		50	(3.14x0.60^2/4)		0.30	4.24		
							4.24	1091.43	4626.57
	Basic Rate	1091.43							
	Total	1091.43							
5	KSRB 7.9 : Providing And fixing **ms grill work** for windows and ventilators using ms flats or ms square rods or combination of ms flats and square rods as per approved design drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials fixtures, labours, and complete as per specifications page no.34 item no.7.9								
	Inside drain	Kgs							
	Perculation pit dia-0.60m		50	0.60	0.60		18.00		
	21 Kgs/Sqm						378.00		
							378.00	100.70	38064.60
	Basic Rate	95.00							
	Area Weightage @ 6%	5.70							
	Total	100.70							
6	KSRRB M2900-1. **Plain cement concrete 1:3:6** mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications MORTH Specification No. 408 KPWD S.R 2018-19 Page No. 254 I.No. 34.1								
		Cum							
	New Drain								
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40	1.10	0.15	17.89		
	5th Cross Road		2	88.00	1.10	0.15	29.04		
	7th cross Road		1	106.00	1.10	0.15	17.49		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00	1.10	0.15	45.87		
	12th cross road		1	15.00	1.10	0.15	2.48		
	Best county-2								
	Vinayaka Temple		1	49.40	1.10	0.15	8.15		
	1st Main Road		1	456.50	1.10	0.15	75.32		
	Cross Road		2	43.00	1.10	0.15	14.19		
	Culverts								

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Subhas Chandra Bose Road								
	8th corss road								
			1	8.80	1.40	0.15	1.85		
	Subhas Chandra Bose Road LHS								
	2nd cross road								
	3rd cross road		1	6.50	1.40	0.15	1.37		
	4th cross road		1	4.00	1.40	0.15	0.84		
	5th cross road		1	6.70	1.40	0.15	1.41		
	6th cross road		1	6.80	1.40	0.15	1.43		
	7th cross road		1	7.00	1.40	0.15	1.47		
	Best County		1	9.00	1.40	0.15	1.89		
	PCC For Kerbs		1	9.00	1.40	0.15	1.89		
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40	0.20	0.075	1.63		
	5th Cross Road		2	88.00	0.20	0.075	2.65		
	7th cross Road		1	106.00	0.20	0.075	1.60		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00	0.20	0.050	2.78		
	12th cross road		1	15.00	0.20	0.075	0.23		
	Best county-2								
	Vinayaka Temple		1	49.40	0.20	0.075	0.77		
	1st Main Road		1	456.50	0.20	0.050	4.57		
	Cross Road		2	43.00	0.20	0.075	1.30		
							238.09	**4479.56**	**1,066,523.26**
	Basic Rate	4226.00							
	Area Weightage @ 6 %	253.56							
	Total Rate	4479.56							
7	Providing and laying plain/reinforced cement concrete for side drains using **M20** nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.**Wall & bottom thickness 15cm** KPWD S.R 2018-19 Page No. 271 I.No. 37.59.2									
		Cum							
	For Raft								
	New Drain								
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40	0.90	0.15	14.63		
	5th Cross Road		2	88.00	0.90	0.15	23.76		
	7th cross Road		1	106.00	0.90	0.15	14.31		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00	1.00	0.15	41.70		
	12th cross road		1	15.00	1.00	0.15	2.25		
	Best county-2								
	Vinayaka Temple		1	49.40	1.00	0.15	7.41		
	1st Main Road		1	456.50	1.00	0.15	68.48		
	Cross Road		2	43.00	1.00	0.15	12.90		
	For DRAIN WALL								
	Jyothi Nagara 2nd stage(Naidu Layout)								

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Jyoti Nagara 2stage main road (LHS)								
	5th Cross Road		2	108.40	0.15	0.60	19.51		
	7th cross Road		4	88.00	0.15	0.60	31.68		
	BHEL LAYOUT 2ND STAGE		2	106.00	0.15	0.60	19.08		
	8th cross road								
	12th cross road		4	139.00	0.15	0.60	50.04		
	Best county-2		2	15.00	0.15	0.60	2.70		
	Vinayaka Temple								
	1st Main Road		2	49.40	0.15	0.60	8.89		
	Cross Road		2	456.50	0.15	0.60	82.17		
	For CULVERT Raft		4	43.00	0.15	0.60	15.48		
	Subhas Chandra Bose Road								
	8th corss road		1	8.80	1.20	0.25	2.64		
	Subhas Chandra Bose Road LHS								
	2nd cross road		1	6.50	1.20	0.25	1.95		
	3rd cross road		1	4.00	1.20	0.25	1.20		
	4th cross road		1	6.70	1.20	0.25	2.01		
	5th cross road		1	6.80	1.20	0.25	2.04		
	6th cross road		1	7.00	1.20	0.25	2.10		
	7th cross road		1	9.00	1.20	0.25	2.70		
	Best County		1	9.00	1.20	0.25	2.70		
	For Culvert Walls								
	Subhas Chandra Bose Road								
	8th corss road		2	8.80	1.20	0.25	5.28		
	Subhas Chandra Bose Road LHS								
	2nd cross road		2	6.50	1.20	0.25	3.90		
	3rd cross road		2	4.00	1.20	0.25	2.40		
	4th cross road		2	6.70	1.20	0.25	4.02		
	5th cross road		2	6.80	1.20	0.25	4.08		
	6th cross road		2	7.00	1.20	0.25	4.20		
	7th cross road		2	9.00	1.20	0.25	5.40		
	Best County		2	9.00	1.20	0.25	5.40		
							467.01	7070.20	3,301,875.31
	Basic Rate	6670.00							
	Area Weightage @ 6 %	400.20							
	Total Rate	7070.20							
8	KSRRB M2200-6. Providing **T.M.T.** steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 **TMT Bars Fe 550(** P-229/28.8.3) PWD SR 2018-19								
		Tn							
	For RCC Drain								
	Total RCC Quantity	Cum					414.00		
		Kg					60.00		
		Kg					24840.00		
							24.84	72940.72	1,811,847.48
	For RCC Drain								
	Total RCC Quantity	Cum					51.00		
		Kg					70.00		
		Kg					3570.00		
							3.57	72940.72	260,398.37

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Basic Rate	68812.00							
	Area Weightage @ 6 %	4128.72							
	Total Rate	72940.72							
9	Providing & laying **precast drain cover slab of 100 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.9 x 0.60 x 0.1)Data rate								
		Sqm							
	New Drain								
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40	0.90		97.56		
	5th Cross Road		2	88.00	0.90		158.40		
	7th cross Road		1	106.00	0.90		95.40		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00	0.90		250.20		
	12th cross road		1	15.00	0.90		13.50		
	Best county-2								
	Vinayaka Temple		1	49.40	0.90		44.46		
	1st Main Road		1	456.50	0.90		410.85		
	Cross Road		2	43.00	0.90		77.40		
	slabs for old drain		1	77.00	0.90		69.30		
	Data Rate	2337.00					**1217.07**	**2337.00**	**2,844,292.59**
10	Providing & laying **precast drain cover slab of 250 mm** thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.60 x 0.25)Data rate								
		Sqm							
	For Culvert								
	Subhas Chandra Bose Road								
	8th corss road		1	8.80	1.20		10.56		
	Data Rate	5418.00					**10.56**	**5418.00**	**57214.08**
11	Providing and fixing pre cast solid cement concrete **kerb stones** made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)								
		No's							
	New Drain								
	Jyothi Nagara 2nd stage(Naidu Layout)								
	Jyoti Nagara 2stage main road (LHS)		1	108.40			108.40		
	5th Cross Road		2	88.00			176.00		
	7th cross Road		1	106.00			106.00		
	BHEL LAYOUT 2ND STAGE								
	8th cross road		2	139.00			278.00		
	12th cross road		1	15.00			15.00		
	Best county-2								

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Vinayaka Temple								
	1st Main Road		1	49.40			49.40		
	Cross Road		1	456.50			456.50		
	New kerbs for old drain		2	43.00			86.00		
			2	60.70			121.40		
			Total Length				1396.70		
			No of kerbs= Total Length/0.45				3103.78	432.48	1,342,321.81
	Basic Rate	408.00							
	Area Weightage @ 6 %	24.48							
	Total Rate	432.48							
12	KSRRB 800-1. Painting **two coats** after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Page No. 180/ Item No. 24.1/ PWD SR 2018-19								
		Sqm							
	Total Length		1	1396.70		0.30	419.10		
							419.10	84.80	35,539.68
	Basic Rate	80.00							
	Area Weightage @ 6 %	4.80							
	Total Rate	84.80							
	ASPHALT ROAD								
13	KSRRB M300-14. **Excavation for roadwork** in all types of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications. MORTH Specification No.301(pg no-143,S.Lno-19.14)KPWD S.R 2018-19								
		Cum							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10	0.55	294.23		
	2nd cross road		1	95.00	6.25	0.52	309.21		
	connecting main road		1	135.70	6.30	0.55	470.20		
	BHEL Layout								
	8th cross road		1	139.00	6.10	0.50	423.95		
	9th cross road		1	191.00	6.10	0.55	640.81		
							2138.40	65.17	139,356.90
	Basic Rate	41.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	3.69							
	Total Rate	65.17							
14	KSRRB 300-58. **Compaction of original ground** with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 (I No-19.64,P No-147)								
		Sqm							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10		534.11		
	2nd cross road		1	95.00	6.25		593.75		
	connecting main road		1	135.70	6.30		854.91		
	BHEL Layout								
	8th cross road		1	139.00	6.10		847.90		
	9th cross road		1	191.00	6.10		1165.10		

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	Basic rate	6.00					3995.77	6.36	25413.10
	Area Weightage 6%	0.36							
	Total	6.36							
15	Construction of **granular sub-base Grading-V as sub-base** and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision. Page No. 153/ Item No. 20.5/ PWD SR 2018-19								
		Cum							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10	0.15	80.25		
	2nd cross road		1	95.00	6.25	0.15	89.06		
	connecting main road		1	135.70	6.30	0.15	128.24		
	BHEL Layout								
	8th cross road		1	139.00	6.10	0.15	127.06		
	9th cross road		1	191.00	6.10	0.15	174.77		
							599.37	1994.92	1,195,694.20
	Basic Rate	1882.00							
	Area Weightage @ 6 %	112.92							
	Total Rate	1994.92							
16	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 Page No. 155/ Item No. 20.18/ PWD SR 2018-19								
		Cum							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10	0.23	123.04		
	2nd cross road		1	95.00	6.25	0.23	136.36		
	connecting main road		1	135.70	6.30	0.23	196.63		
	BHEL Layout								
	8th cross road		1	139.00	6.10	0.23	195.02		
	9th cross road		1	191.00	6.10	0.23	267.97		
							919.02	2001.28	1,839,221.15
	Basic Rate	1888.00							
	Area Weightage @ 6 %	113.28							
	Total Rate	2001.28							
17	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM ,including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per Specifications. MORTH Specification No. 502 Complete with all lead and lift and as per the direction of the Engineer-in-Charge. Page No. 158/ Item No. 21.6/ PWD SR 2018-19 Issue Rates								
		Sqm							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10		534.11		

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
	2nd cross road								
	connecting main road		1	95.00	6.25		593.75		
	BHEL Layout		1	135.70	6.30		854.91		
	8th cross road								
	9th cross road		1	139.00	6.10		847.90		
			1	191.00	6.10		1165.10		
							3995.77	29.68	118,594.45
	Basic Rate	28.00							
	Area Weightage @ 6 %	1.68							
	Total Rate	29.68							
18	KSRRB M500-17. Providing and laying **dense graded bituminous macadam** using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. Clause 505 of morth V revision using 40/60 TPH capacity H.M.P. with mechanical paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen. Page No. 160/ Item No. 21.17.6/ PWD SR 2018-19 Issue Rates								
		Cum							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10	0.05	26.75		
	2nd cross road		1	95.00	6.25	0.05	29.69		
	connecting main road		1	135.70	6.30	0.05	42.71		
	BHEL Layout								
	8th cross road		1	139.00	6.10	0.05	42.40		
	9th cross road		1	191.00	6.10	0.05	58.26		
							199.80	6407.70	1,280,232.83
	Basic Rate	6045.00							
	Area Weightage @ 6 %	362.70							
	Total Rate	6407.70							
19	KSRRB 500-2. **Cleaning the existing black** topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 Page No. 158/ Item No. 21.2/ PWD SR 2018-19								
		Sqm							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10		534.11		
	2nd cross road		1	95.00	6.25		593.75		
	connecting main road		1	135.70	6.30		854.91		
	BHEL Layout								
	8th cross road		1	139.00	6.10		847.90		
	9th cross road		1	191.00	6.10		1165.10		
							3995.77	5.30	21,177.58
	Basic Rate	5.00							
	Area Weightage @ 6 %	0.30							
	Total Rate	5.30							
20	KSRRB 500-7. Providing and applying **tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5 Page No. 158/ Item No. 21.7/ PWD SR 2018-19 Issue Rates								

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
		Sqm							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10		534.11		
	2nd cross road		1	95.00	6.25		593.75		
	connecting main road		1	135.70	6.30		854.91		
	BHEL Layout								
	8th cross road		1	139.00	6.10		847.90		
	9th cross road		1	191.00	6.10		1165.10		
							3995.77	12.72	50,827.56
	Basic Rate	12.00							
	Area Weightage @ 6 %	0.72							
	Total Rate	12.72							
21	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision. -using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen (Pg:162, It.No-21.22.6 PWD SR:2018-19)Issue Rates								
		Cum							
	Jyoti Nagara 2stage								
	5th cross road		1	87.70	6.10	0.03	16.05		
	2nd cross road		1	95.00	6.25	0.03	17.81		
	connecting main road		1	135.70	6.30	0.03	25.62		
	BHEL Layout								
	8th cross road		1	139.00	6.10	0.03	25.44		
	9th cross road		1	191.00	6.10	0.03	34.95		
							119.87	7355.34	881,696.37
	Basic Rate	6939.00							
	Area Weightage @ 6 %	416.34							
	Total Rate	7355.34							
22	KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 Page No. 182/ Item No. 24.15 PWD SR 2018-19								
		Sqm							
	Jyoti Nagara 2stage								
	5th cross road		2.5	87.70	0.10		21.93		
	2nd cross road		2.5	95.00	0.10		23.75		
	connecting main road		2.5	135.70	0.10		35.48		
	BHEL Layout								
	8th cross road		2.5	139.00	0.10		34.75		
	9th cross road		2.5	191.00	0.10		47.75		
							163.66	454.74	74,420.47
	Basic Rate	429.00							
	Area Weightage @ 6 %	25.74							
	Total Rate	454.74							

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount (Rs)
								Sub Total-A	16,751,417.35
								Tender Premium 5%	837,570.87
								GST 12%	2,010,170.08
								DPR 1%	200,000.00
								PMC 1%	200,000.00
								Miscellaneous	841.70
								Total	20,000,000.00

VSR CIVIL INFRA PVT LTD BANGALORE Consultant

Assistant Engineer
Ward No. 3

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪವಿಭಾಗ ಸಿವಿಲ್ ವಿಭಾಗ.
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬೆಂಗಳೂರು-106

Asst Executive Engineer
Yelahanka Sub-Division

Executive Engineer
Yelahanka Divison